

HYDRAULIC POWER DEVELOPMENT
ON
EAST CANADA CREEK, NEW YORK

G. W. BUCK
W. J. DEVENY
G. D. LETTERMANN

ARMOUR INSTITUTE OF TECHNOLOGY
1910

621.28
B 855

UNIVERSITY LIBRARIES
of Technology
Illinois Institute



AT 175

Buck, G. W.

Proposed hydraulic power
development on East Canada

FOR USE IN LIBRARY ONLY

7. 10. 1911
10. 10. 1911
11. 10. 1911
12. 10. 1911
13. 10. 1911
14. 10. 1911
15. 10. 1911
16. 10. 1911
17. 10. 1911
18. 10. 1911
19. 10. 1911
20. 10. 1911
21. 10. 1911
22. 10. 1911
23. 10. 1911
24. 10. 1911
25. 10. 1911
26. 10. 1911
27. 10. 1911
28. 10. 1911
29. 10. 1911
30. 10. 1911
31. 10. 1911
32. 10. 1911
33. 10. 1911
34. 10. 1911
35. 10. 1911
36. 10. 1911
37. 10. 1911
38. 10. 1911
39. 10. 1911
40. 10. 1911
41. 10. 1911
42. 10. 1911
43. 10. 1911
44. 10. 1911
45. 10. 1911
46. 10. 1911
47. 10. 1911
48. 10. 1911
49. 10. 1911
50. 10. 1911
51. 10. 1911
52. 10. 1911
53. 10. 1911
54. 10. 1911
55. 10. 1911
56. 10. 1911
57. 10. 1911
58. 10. 1911
59. 10. 1911
60. 10. 1911
61. 10. 1911
62. 10. 1911
63. 10. 1911
64. 10. 1911
65. 10. 1911
66. 10. 1911
67. 10. 1911
68. 10. 1911
69. 10. 1911
70. 10. 1911
71. 10. 1911
72. 10. 1911
73. 10. 1911
74. 10. 1911
75. 10. 1911
76. 10. 1911
77. 10. 1911
78. 10. 1911
79. 10. 1911
80. 10. 1911
81. 10. 1911
82. 10. 1911
83. 10. 1911
84. 10. 1911
85. 10. 1911
86. 10. 1911
87. 10. 1911
88. 10. 1911
89. 10. 1911
90. 10. 1911
91. 10. 1911
92. 10. 1911
93. 10. 1911
94. 10. 1911
95. 10. 1911
96. 10. 1911
97. 10. 1911
98. 10. 1911
99. 10. 1911
100. 10. 1911

PROPOSED HYDRAULIC POWER DEVELOPMENT.

ON

EAST CANADA CREEK.

AT

INGHAM MILLS, NEW YORK.

A T H E S I S

Presented By

G. Warner Buck.

J. J. Steency.

George D. Lettermann.

To The

PRESIDENT AND FACULTY

OF

ARMOUR INSTITUTE OF TECHNOLOGY

For the Degree of

Bachelor of Science In Civil Engineering

Having Completed The Prescribed Course

In

Civil Engineering.

ILLINOIS INSTITUTE OF TECHNOLOGY
PAUL V. GALVIN LIBRARY
35 WEST 33RD STREET
CHICAGO, IL 60616

27
Alfred E. Philip
Prof. of Civil Engineering
L. M. Raymond
Dean Eng. Studies
L. C. Morison, Trans. of Eng. Studies

PROPOSED HYDRAULIC POWER DEVELOPMENT.

ON

EAST CANADA CREEK.

AT

INGHAM MILLS, NEW YORK.

A T H E S I S

Presented By

W. Warner Buck,

John F. Warner,

George A. Letcher,

To The

PRESIDENT AND FACULTY

OF

ARMOUR INSTITUTE OF TECHNOLOGY

For the Degree of

Bachelor of Science in Civil Engineering

Having Completed The Prescribed Course

In

Civil Engineering.

ILLINOIS INSTITUTE OF TECHNOLOGY
PAUL V. GALVIN LIBRARY
35 WEST 33RD STREET
CHICAGO, IL 60616

John F. Warner
George A. Letcher
W. Warner Buck
John F. Warner
George A. Letcher
W. Warner Buck

INTRODUCTION.

INDEX.

INTRODUCTION -----	1
HYDRAULIC CONDITIONS AND DEVELOPMENT -----	3
THE DAM -----	8
THE PIPE LINE -----	16
THE POWER-HOUSE -----	21
INGHAM MILLS AND VICINITY -----	Plate 1
SITE OF PROPOSED PROJECT -----	" 2
PROFILE OF RETAINING SECTION -----	" 3
PROFILE OF SPILLWAY SECTION -----	" 4
DOWN-STREAM ELEVATION OF DAM -----	" 5
CROSS-SECTION OF DAM, SPILLWAY AND INTAKE -----	" 6
SLUICE GATE AND OPERATING STAND -----	" 7
GENERAL SECTIONS OF PIPE LINE AND SURGE TANK -----	Plates 8-10
GENERAL SECTIONS OF POWER-HOUSE -----	" 13-18

the water supply and that obtain on the drainage area of the stream on which the proposed hydraulic power development is projected. The present condition of these factors is readily obtainable by careful observation and surveys, but the most difficult and **22141** most important information needed for the correct understanding of the project, is the variations from the present conditions that have occurred in the past and that are therefore liable to re-occur in the

INDEX.

1	INTRODUCTION
2	HYDRAULIC CONDITIONS AND DEVELOPMENT
3	THE DAM
4	THE PIPE LINE
5	THE POWER-HOUSE
6	INGHAM MILLS AND VICINITY
7	SITE OF PROPOSED PROJECT
8	PROFILE OF RETAINING SECTION
9	PROFILE OF SPILLWAY SECTION
10	DOWN-STREAM ELEVATION OF DAM
11	CROSS-SECTION OF DAM, SPILLWAY AND INTAKE
12	SLUICE GATE AND OPERATING STAND
13-14	GENERAL SECTIONS OF PIPE LINE AND SURGE TANK
15-16	GENERAL SECTIONS OF POWER-HOUSE

INTRODUCTION.

Natural water powers have long held an important place among the sources of energy available for industrial purposes. Within the past few years, the progress made in the methods for converting mechanical into electrical energy, and the increase in the distance to which the latter can be economically transmitted, have led to the utilization of many water powers. The advantages to any community of cheap and reliable power are so great, that a steady growth of this kind is to be expected. Apart from manufacturers of all kinds, the purely municipal purposes of lighting and electric traction will of themselves, absorb a considerable amount of power.

The investigation of any water power project should include a careful study of all available data relating to the topographical and meteorological factors that effect the water supply and that obtain on the drainage area of the stream on which the proposed hydraulic power development is projected. The present condition of these factors is readily obtainable by careful observation and surveys, but the most difficult and yet the most important information needed for the correct understanding of the project, is the variations from the present conditions that have occurred in the past and that are therefore liable to re-occur in the future.

Natural water powers have long held an important place among the sources of energy available for industrial purposes. Within the past few years, the progress made in the methods of harnessing water power into electrical energy, and the knowledge of the relation of water to the utilization of such water for industrial purposes, has brought about a revolution in the kind of power available. The progress made in the methods of harnessing water power into electrical energy, and the knowledge of the relation of water to the utilization of such water for industrial purposes, has brought about a revolution in the kind of power available. The progress made in the methods of harnessing water power into electrical energy, and the knowledge of the relation of water to the utilization of such water for industrial purposes, has brought about a revolution in the kind of power available.

The investigation of the water power resources of the United States is a subject of great importance to the Nation. The geographical and meteorological factors that affect the water supply and that obtain in the drainage area of the river on which the proposed hydraulic power development is projected. The present condition of these factors is readily obtainable by careful observation and survey, but the most difficult and yet the most important information needed for the correct understanding of the project, is the conditions from the present conditions that have occurred in the past and that are therefore liable to re-occur in the future.

On the correct interpretation of the available data the success of the project, or at least the economy of the installation, depends, especially if, as is usually the case, it is desired to develop the plant to its economical maximum.

The state of New York is richly endowed with natural advantages favorable to a full utilization of its vast water power resources. On its many rivers, especially those springing from the prolific water producing region of the Adirondacks, there are many advantageous sites for creating new developments, and for increasing by artificial storage the capacity of existing power plants.

Ingham Mills is about five miles from Little Falls, New York and is reached by a branch of the New York Central Railroad.

The situation of Ingham Mills is exceptionally advantageous for a hydraulic power plant, being in the center of a fairly well developed manufacturing district. Within a radius of thirty miles are Gloversville, Johnstown, Ponda and Canajoharie. The present use of electric current for lighting, traction and manufacturing purposes within this radius is great and the constantly increasing demand insures a large market.

The object of this thesis is the profitable development

As the correct interpretation of the available data the
success of the project, or at least the economy of the
development, depends, especially in this latter case,
upon, it is desired to review the facts in this connection.

The state of New York is richly endowed with natural
advantages favorable to a full utilization of its water
power resources. On its many rivers, especially those
springing from the prolific water-producing regions of the
Adirondacks, there are many advantageous sites for creating
new developments, and for increasing by artificial storage
the capacity of existing power plants.

Ingham Mills is about five miles from Little Falls, New
York and is reached by a branch of the New York Central
Railroad.

The situation of Ingham Mills is exceptionally ad-
vantageous for a hydraulic power plant, being in the center
of a fairly well developed manufacturing district. Within
a radius of thirty miles are Glensville, Johnson, Tonawanda
and Gettysburg. The present use of electric current for
lighting, traction and manufacturing purposes within this
radius is great and the constantly increasing demand further a-
heads is rapid.

The object of this thesis is the probable development

of the available water power of East Canada creek at Ingham Mills for the purpose of partially supplying this demand, and it is with the preliminary investigation, design and construction of such project that we shall confine ourselves.

HYDRAULIC CONDITIONS AND DEVELOPMENT.

The requisites of a reservoir site are numerous, among which may be mentioned the following:-

1. There must be an available water supply sufficient to fill the basin.
 2. There must be a basin to hold this supply.
 3. There must be a good dam site.
 4. There must be suitable materials from which to construct a dam.
 5. The foundation must be able to satisfactorily sustain the dam.
 6. There must be available lands upon which to put the water.
 7. The entire project must be on a commercial basis.
- A comprehensive and detailed study of existing topographical maps and hydrographic data on the East Canada creek in the Mohawk system indicated promising opportunities for power development and storage.

East Canada creek is the second important tributary of

of the available water power of West Canada creek at Lathrop
 Mills for the purpose of partially supplying this demand, and
 it is with the preliminary investigation, location and con-
 struction of such project that we shall continue our survey.

HYDRAULIC CONDITIONS AND DEVELOPMENT.

The regulation of a reservoir site and dam, and

which may be mentioned the following:-

1. There must be an available water supply sufficient
 to fill the basin.
2. There must be a basin to hold this supply.
3. There must be a good dam site.
4. There must be suitable materials from which to
 construct a dam.
5. The foundation must be able to satisfactorily
 sustain the dam.
6. There must be available lands upon which to put
 the water.
7. The entire project must be on a commercial basis.
 A comprehensive and detailed study of existing
 topographical maps and hydrographic data on the West Canada
 creek in the North-western provinces and territories
 for power development and storage.
8. West Canada creek is the second largest tributary of

the Mohawk. This creek rises in the south western part of Hamilton County, and flows southerly between Herkimer and Fulton Counties, joining the Mohawk at East creek, about seven miles from Little Falls. Its drainage area above Ingham Mills comprising approximately two hundred and seventy three square miles, contains about thirty small lakes and ponds and numerous swamps and marshes in the region of the head waters. A considerable part of the basin is timber covered. The underlying rock is granitic gneiss in the upper portion of the basin, with limestone in some places. Heavy accumulations of snow occur during the winter.

The principal tributary of East Canada creek is Big Sprite creek, which is the outlet of the East Canada Lakes. The distance from the East Canada Lake outlet to its junction with East Canada creek, is about nine miles. In the first four miles there is a fall of three hundred and ninety feet. The remaining five miles to its mouth, has a fall of two hundred and forty-five feet.

The second tributary of East Canada creek is Spruce creek, which enters it one mile above Dolgeville and drains an area of fifty square miles. The total length from its source in the Eaton Mill pond to its mouth, is about nine miles; the total fall in this distance being approximately five hundred and fifty feet. Just below the Eaton Mill

the Mohawk. This creek rises in the south western part of Hamilton County, and flows southerly between Hamilton and Fulton Counties, joining the Mohawk at East Creek, about seven miles from Little Falls. Its drainage area above Ingham Mills comprising approximately two hundred and seventy three square miles, contains about thirty small lakes and ponds and numerous swamps and marshes in the region of the head waters. A considerable part of the basin is timber covered. The underlying rock is granitic gneiss in the upper portion of the basin, with limestone in some places. Heavy accumulations of snow occur during the winter.

The principal tributary of East Canada Creek is Big Spruce Creek, which is the outlet of the East Canada Lakes. The distance from the East Canada Lakes outlet to its junction with East Canada Creek, is about nine miles. In the first four miles there is a fall of three hundred and ninety feet. The remaining five miles to its mouth, has a fall of two hundred and forty-five feet.

The second tributary of East Canada Creek is Spruce Creek, which enters it one mile above Littleville and drains an area of fifty square miles. The total length from its source in the Adirondacks to its mouth, is about nine miles; the total fall in this distance being approximately five hundred and fifty feet. Just below the Adirondack

pond there is a fall of one hundred and eighty feet in two thousand feet. At Salisbury Center, Spruce creek falls eighty-five feet in about nine hundred feet. A number of water power privileges are developed at this point. There is a total of twelve small dams on Spruce creek giving an aggregate fall of about one hundred and eighty feet.

The mean annual rainfall on the East Canada water-shed above Ingham Mills for the past ten years, as disclosed by studies of the United States Weather Bureau reports, is 40 inches.

The conditions on which the proposed development is based were obtained from the various water supply papers of the United States Geological Survey for the past ten years (1899-1909 inclusive), containing the maximum and minimum daily and monthly discharges of the stream at Dolgeville about three miles up stream from Ingham Mills. At this point the discharge of the stream over the dam of the Herkimer County Light and Power Company, is computed from a discharge curve based on United States Geological Survey experiments.

About a mile above Ingham Mills, Gillette creek having a drainage area of approximately seventeen square miles, flows into East Canada creek. The drainage area of the East Canada creek above Dolgeville is two hundred and fifty-six square miles; thus the total area drained by the stream above

pond there is a fall of one hundred and eighty feet in two

five feet in about nine hundred feet. A number of water

power privileges are developed at this point. There is a

total of twelve small dams in between giving an

aggregate fall of about one hundred and eighty feet.

The mean annual rainfall on the West Canada watershed

above Ingham Mills for the past ten years, as disclosed by

studies of the United States Weather Bureau reports, is 40

inches.

The conditions on which the proposed development is

based were obtained from the various water supply papers of

the United States Geological Survey for the past ten years

(1909-1929 inclusive), containing the maximum and minimum

daily and monthly discharges of the stream at Delaportville about

three miles up stream from Ingham Mills. At this point the

discharge of the stream over the dam of the Northern Company

Light and Power Company, is computed from a discharge curve

based on United States Geological Survey experiments.

About a mile above Ingham Mills, Little Creek having

a drainage area of approximately seven hundred acres, falls

flows into West Canada creek. The drainage area of the West

Canada creek above Delaportville is two hundred and fifty-six

square miles; thus the total area drained by the stream above

Ingham Mills is two hundred and seventy-three square miles.

The data as to the discharge at Ingham Mills, were determined by multiplying the various discharge measurements obtained at Dolgeville by the constant $\frac{273}{256} = 1.06$; 273 being the total drainage area in square miles above Ingham Mills and 256 being the area above Dolgeville. This factor took into account the additional discharge due to Gillette creek. From these data mean monthly discharge curves were plotted. A curve was also plotted showing the daily discharge of the stream for the year 1906, which was a year of relatively high flood.

The flow of the stream at Ingham Mills varies from a maximum of 3280 second feet to a minimum of 90 second feet. A dam will be constructed at Stewart Landing near the head of Big Sprite creek by means of which a large service reservoir of 500,000,000 gallons capacity will be created. The function of this reservoir is to augment considerably the minimum discharge of the stream at Ingham Mills.

By constructing a dam across the valley where the stream is about ninety feet wide, a head of one hundred and twenty-five feet can be utilized. It was concluded that using a flow of two hundred and fifty second feet for twenty-four hours, or six hundred second feet for a period of ten hours the maximum power of the stream could be developed throughout the entire year without the necessity of an emergency steam

Ingham Mills is two hundred and seventy-three up river miles.

The data as to the discharge at Ingham Mills, were

determined by multiplying the various discharge measurements

obtained at Polgevillie by the constant $\frac{282}{258} = 1.09$; was

being the total discharge area in square miles above Ingham

Mills and 258 being the area above Polgevillie. This factor

took into account the additional discharge due to dilution

over. From these data mean monthly discharge curves were

plotted. A curve was also plotted showing the daily dis-

charge of the stream for the year 1908, which was a year of

average discharge.

The flow of the stream at Ingham Mills varies from a

maximum of 3250 second feet to a minimum of 60 second feet.

A dam will be constructed at Stewart Landing near the head of

Big Spring creek by means of which a large storage reservoir

of 500,000,000 gallons capacity will be created. The

function of this reservoir is to augment considerably the

minimum discharge of the stream at Ingham Mills.

By constructing a dam across the valley where the stream

is about ninety feet wide, a head of one hundred and twenty-

five feet can be utilized. It was concluded that using a

flow of two hundred and fifty second feet for twenty-four

hours, or six hundred second feet for a period of ten hours

the maximum power of the stream could be developed throughout

the entire year without the necessity of any artificial aid.

plant.

The available power was determined as follows:

Let Q = discharge in second feet.

H = available head.

W = weight of a cubic foot of water

E = efficiency of water wheels

$$\text{then Horse Power} = \frac{Q \times H \times W \times E}{550}$$

or

$$\text{H.P.} = \frac{600 \times 125 \times 62.5 \times .85}{550} = 7200$$

The proposed development consists of a gravity dam, one hundred and twenty-five feet in height. The main conduit to be a pipe line with an internal diameter of twelve feet. The total length is eleven hundred feet of riveted steel pipe provided with a surge tank fifty eight feet high and forty feet in diameter. The function of the surge tank is to relieve the pipe line of excessive pressures due to a sudden closing of the gates in the water wheels, following a quick drop in the demand for power and also to maintain pressures and speed regulation in the station when sudden demands are made for water. The top of the surge tank rises to twenty-five feet above high water level above dam. From the surge tank there will be three riveted steel pipes, each six feet in diameter and four hundred feet in length, leading directly to the power house. The total hydrostatic head from the flow line of the reservoir to centers of receivers, will be one hundred and twenty-five feet.

The available power was determined as follows:

Let Q = discharge in second feet.

H = available head.

W = weight of a cubic foot of water.

E = efficiency of water wheel.

then Horse Power = $\frac{Q \times H \times W \times E}{550}$

or

$$H.P. = \frac{Q \times H \times 62.5 \times .85}{550}$$

The proposed development consists of a gravity dam, one hundred and twenty-five feet in height. The main conduit to be a pipe line with an internal diameter of twenty feet. The total length is eleven hundred feet of riveted steel pipe provided with a surge tank fifty eight feet high and forty feet in diameter. The function of the surge tank is to absorb the line of excessive pressure due to a sudden closing of the gates in the water wheel, following a quick drop in the demand for power and also to maintain pressure and avoid regulation in the station when sudden demands are made for water. The toe of the surge tank rises to twenty-five feet above high water level above dam. From the surge tank there will be three riveted steel pipes, each six feet in diameter and four hundred feet in length. Leading directly to the power house. The total hydrostatic head from the flow line of the reservoir to center of penstock, will be one hundred and twenty-five feet.

DESIGN OF DAM.

A topographical survey using the stadia method, was made of the valley in the immediate vicinity of Ingham Mills. The general location of the dam was determined by the topography of the valley, but it required considerable study to fix its exact site. A number of test pits were sunk to bed rock in the stream by means of cofferdam construction. Limestone of a fairly compact texture was encountered.

The location chosen combines the advantages of a fairly short dam with a comparatively high position of bed rock. The cross section is shown on Plate 3.

The dam will be built of solid concrete masonry and founded on bed rock. Its length measured on the crest is five hundred and ten feet. It will be one hundred and twenty-three feet above the present river bed and its foundation will extend two feet lower, making a total height of one hundred and twenty-five feet above bed rock with a batter of 1 in 12.5. Along the west bank of the stream at the site of the dam, there is a pocket about ten feet deep and five feet wide, caused by the erosive action of the stream at this point. In order to eliminate an unnecessary amount of rock excavation, this pocket will be filled with concrete.

At each end of the dam concrete core-walls, having a batter of 1 in 20 and placed two feet in rock extend into the adjoining sides of the valley in such a manner as to form

A topographical survey within the limits defined, was made of the valley in the immediate vicinity of Indian Wells. The general location of the dam was determined by the topography of the valley, but it required considerable study to fix its exact site. A number of test pits were sunk to bed rock in the stream by means of ordinary construction. The location of a fairly compact center was established. The location chosen combines the advantages of a fairly good dam with a comparatively high position of bed rock. The cross section is shown on Plate 2.

The dam will be built of solid concrete masonry and founded on bed rock. Its length measured on the crest is five hundred and ten feet. It will be one hundred and twenty-three feet above the present river bed and its foundation will extend two feet lower, making a total height of one hundred and twenty-five feet above bed rock with a batter of 1 in 12.5. Along the west bank of the stream at the side of the dam, there is a gully about ten feet deep and five feet wide, caused by the erosive action of the stream at this point. In order to eliminate an unnecessary source of rock excavation, this gully will be filled with concrete.

At each end of the dam concrete core-walls, having a batter of 1 in 20 and placed two feet in rock extend into the adjoining sides of the valley in such a manner as to form

a perfectly safe seal and thus prevent the water from escaping around the ends of the structure.

A spillway for carrying off flood water will be constructed on the east end of the dam. The length of this waste-way is two hundred and sixty feet and its crest is ten feet lower than that of the retaining section. It is twenty-four feet in height, having a vertical up-stream face and an ogee down-stream face. Concrete of a 1-2-4 mixture will be used in constructing both the dam and spillway.

An intake for supplying the conduit will be placed near the west end of the dam on the up-stream side. At this intake the water is controlled by a twelve foot circular sluice gate. This gate has a non-rising stem, which passes through an operating stand on top of the dam. The stand is geared so that it may be operated by hand. Screens inclined at an angle of approximately sixty degrees to the horizontal, are placed at the entrance of the intake to protect the intake pipe. Provision is made for repairing the sluice gate by means of emergency stop logs. Access can be had to the sluice gate chamber by an iron ladder projecting from the concrete wall and extending from the top to the pit of the chamber. Drainage of the chamber is provided by a twelve inch drain pipe, extending under the intake pipe and through to the down-stream side of the dam.

a perfectly safe and thus prevent the water from overflowing around the ends of the structure.

A spillway for carrying off flood water will be constructed on the east side of the dam. The spillway will be two hundred and sixty feet and the crest is ten feet lower than that of the retaining section. It is twenty-four feet in height, having a vertical upstream face and an ogee downstream face. Concrete of a 1:2:4 mixture will be used in constructing both the dam and spillway.

An intake for supplying the conduit will be placed near the west end of the dam on the upstream side. At this intake the water is controlled by a vertical gate similar to those used in this part has a non-rising stem, which passes through an operating stand on top of the dam. The stand is geared so that it may be operated by hand. Gears are inclined at an angle of approximately sixty degrees to the horizontal, the placed at the entrance of the intake to protect the intake pipe. Provision is made for repairing the intake gate by means of emergency stop logs. Access can be had to the intake gate chamber by an iron ladder provided for the concrete wall and extending from the top of the intake chamber. Drainage of the chamber is provided by a twelve inch drain pipe, extending under the intake pipe and through to the downstream side of the dam.

The dam is designed purely as a gravity structure, and the usual standards of strength and stability are followed. The water was assumed to extend from the top of the dam to bed rock, but was not supposed to penetrate beneath and exert an upward pressure.

The profile as shown on Plate 3 is divided into six sections by horizontal joints. The centers of gravity of courses 1 to 6 are found in the usual manner, the vertical section of each course being assumed to form a trapezoid.

The retaining section was designed as follows:-

Reservoir Empty: The line of pressure was determined in the following manner:- The center of gravity of sections 1 and 2 are joined by a line and the center of gravity of these two combined sections found, as shown on Plate 3. A line is drawn vertically downward from the center of gravity of sections 1 and 2. Where this vertical line intersects the line bb is one point in the line of pressure. In a similar manner the points where this line intersects the other joints are found. When the reservoir is empty, the only forces acting on the dam, are the weights of the different courses 1 to 6, each being applied at the center of gravity of the respective course.

Reservoir Full: The line of resultant pressure was determined as follows:- The pressure of the water acts at a point equal to one third the height from the base of section 2. This distance

The dam is designed purely as a gravity structure, and the usual standards of strength and stability are followed. The water was assumed to extend from the top of the dam to bed rock, but was not supposed to penetrate beneath the dam.

The profile as shown on Plate 1 is divided into six sections of horizontal joints. The center of gravity of each section of each course being assumed to be at its geometric center.

The retaining section was designated as follows:-

Retaining Wall: The line of pressure was determined in the following manner:- The center of gravity of sections 1 and 2 are joined by a line and the center of gravity of these two combined sections found, as shown on Plate 2. A line is

drawn vertically downward from the center of gravity of sections 1 and 2. When this vertical line intersects the line AB is one foot in the line of pressure. In a similar manner the point where this line intersects the other joints are found. When the pressure is equal, the only force acting on the dam, are the weights of the different courses 1 to 5, each being applied at the center of gravity of the respective course.

Retaining Wall: The line of resultant pressure was determined as follows:- The pressure of the water was assumed to be the third the height from the base of section 1. This distance

is laid off to scale on the line drawn vertically downward through the center of gravity of sections 1 and 2. From this point a perpendicular line equal in length to the water pressure, is drawn. A line equal in length to the weight of the masonry, is drawn perpendicular to the line of water pressure. Where the resultant of the line representing the water pressure and the weight of masonry respectively, intersects the joint bb is one point in the line of resultant pressure. Similarly, the points where this resultant intersects the other joints are found.

The resultant of all joints is kept within the middle third, so that there are no tensile stresses.

The factors of safety are the following: As to Overturning:- The moment of the forces, which resist over-turning when taken about the down-stream edge of the dam at any elevation are more than twice as great as the moment of over-turning at the same point.

As to Sliding:- A coefficient of friction of .85 in the concrete masonry was assumed. Conservative engineering practice shows that this factor is considered amply safe in case of a concrete dam in which there will be no joints properly speaking, but on the contrary, considerable cohesive strength.

is laid off to scale on the line known vertically downward
 through the center of gravity of sections I and II. From this
 point a perpendicular line equal in length to the water
 pressure, is drawn. A line equal in length to the weight of
 the masonry, is drawn perpendicular to the line of water
 pressure. Where the resultant of the line representing the
 water pressure and the weight of masonry respectively, in-
 tersects the joint AB is one point in the line of resultant
 pressure. Similarly, the points where this resultant inter-
 sects the other joints are found.

The resultant of all joints is kept within the middle
 third, so that there are no tensile stresses.

The factors of safety are the following: As to over-
 turning:- The moment of the forces, which resist over-
 turning about the outer edge of the dam at any eleva-
 tion are more than twice as great as the moment of over-
 turning at the same point.

As to sliding:- A coefficient of friction of .45 in the
 concrete masonry was assumed. Considerative engineering
 practice shows that this factor is considered small, and in
 case of a concrete dam, in which there will be no joints, proper
 by weighing, but on the contrary, considerably less.

Spillway Section: The curve on the down-stream side was determined by plotting the parabolic curve, using the equation of the parabola

$$X^2 = 2 P Y. \quad (1)$$

where 2 P by experiment was found to be equal to 1.98 H; the height of water flowing over the crest of the spillway being assumed as five feet, then $H = \frac{H}{8} + 5$

$$\therefore H = 5.710.$$

substituting the above values in (1)

$$\text{Therefore: } X^2 = (1.98 \times 5.71) Y.$$

The line of resultant pressure of the spillway section, the profile of which is shown on Plate 4 was determined in the same manner as that followed in the design of the retaining section.

In order to increase the height of the spillway section during low water, so as to dispose of a higher head than would be otherwise possible at a moment when such increase of head is most opportune, flash boards were designed so as to give way when the water reaches the desired elevation. These flash boards are held in place by "Wayne" iron pins fitted in pipe sleeves in the concrete. When a fiber stress of 69500 pounds per square inch is reached, the pins fail.

Spillway Section: The curve on the downstream side was

determined by plotting the parabolic curve, using the

equation of the parabola

$$(1) \quad X^2 = 2 P Y.$$

where P by experiment was found to be equal to 1.68 ft; the

height of water flowing over the crest of the spillway being

assumed as five feet, then $X = 4.18$ ft.

$$H = 5.710.$$

substituting the above values in (1)

$$\text{Therefore: } X^2 = (1.68 \times 5.71) Y.$$

The line of resultant pressure of the spillway section,

the profile of which is shown on Plate was determined in the

same manner as that followed in the design of the retaining

structure.

In order to increase the height of the spillway section

during low water, so as to dispose of a higher head than would

be otherwise possible at a moment when such increase of head

is most opportune, flash boards were designed so as to give

way when the water reaches the desired elevation. These flash

boards are held in place by "Wynes" iron pins fitted in pipe

staves in the concrete. When a flash is raised to 84000 pounds

per square inch is removed, the pins fall.

CALCULATIONS.

RETAINING SECTION:-

Area of section 1: $\frac{14}{2} [12 + 13.1] = 175.7 \text{ sq. ft.}$

Area of section 2: $\frac{11}{2} [13.1 + 18] = 171 \text{ sq. ft.}$

Weight of sections 1 and 2: $[175.7 + 171] 150 = 52012.3 \text{ lbs/cu. ft.}$

Water pressure at 25 foot depth: $\frac{wh^2}{2} = \frac{62.5 \times (25)^2}{2} = 19530 \text{ lbs/sq. ft.}$

Resultant water pressure: 56000 lbs. per square foot.

Area of section 3: $\frac{25}{2} [18 + 34] = 650 \text{ sq. ft.}$

Weight of sections 1, 2 and 3: $[175.7 + 171 + 650] 150 = 149513 \text{ lbs/cu. ft.}$

Water pressure at 50 foot depth: $\frac{62.5 \times 50^2}{2} = 83125 \text{ lbs./sq. ft.}$

Resultant pressure: 170400 lbs. per square foot.

Area of section 4: $\frac{25}{2} [34 + 52] = 1075 \text{ sq. ft.}$

Weight of sections 1, 2, 3 and 4: $[996.75 + 1075] 150 = 31076 \text{ lbs/cu. ft.}$

Water pressure at 75 foot depth: $\frac{62.5 \times 75^2}{2} = 175780 \text{ lbs./sq. ft.}$

Resultant pressure: 357600 lbs. per square foot

Area of section 5: $\frac{25}{2} [52 + 70] = 1525 \text{ sq. ft.}$

Weight of sections 1, 2, 3, 4 and 5: $[2071.75 + 1525] 150 = 539513 \text{ lbs}$

Water pressure 100 foot depth: $\frac{62.5 \times 100^2}{2} = 312500 \text{ lbs./sq. ft.}$

Resultant pressure: 623500 lbs. per square foot.

Area of section 6: $\frac{25}{2} [70 + 88] = 1975 \text{ sq. ft.}$

Weight of sections 1, 2, 3, 4, 5 and 6: $[3596.75 + 1975] 150 = 835763$

Water pressure 125 foot depth: $\frac{62.5 \times 125^2}{2} = 488280 \text{ lbs/sq. ft.}$

Total resultant pressure: 966700 lbs. per square foot.

CALCULATION.

SECTION 1.

$$\text{Area of section 1: } \frac{1}{2} [12+12] = 12 \text{ sq. ft.}$$

$$\text{Area of section 2: } \frac{1}{2} [12+12] = 12 \text{ sq. ft.}$$

$$\text{Weight of sections 1 and 2: } [12+12] \times 150 = 3600 \text{ lbs.}$$

$$\text{Water pressure at 20 foot depth: } \frac{62.5 \times 20}{2} = 625 \text{ lbs.}$$

Resultant pressure: 3600 lbs. per square foot

$$\text{Area of section 3: } \frac{1}{2} [12+12] = 12 \text{ sq. ft.}$$

$$\text{Weight of sections 1, 2 and 3: } [12+12+12] \times 150 = 5400 \text{ lbs.}$$

$$\text{Water pressure at 30 foot depth: } \frac{62.5 \times 30}{2} = 937.5 \text{ lbs.}$$

Resultant pressure: 17040 lbs. per square foot

$$\text{Area of section 4: } \frac{1}{2} [12+12] = 12 \text{ sq. ft.}$$

$$\text{Weight of sections 1, 2, 3 and 4: } [12+12+12+12] \times 150 = 7200 \text{ lbs.}$$

$$\text{Water pressure at 40 foot depth: } \frac{62.5 \times 40}{2} = 1250 \text{ lbs.}$$

Resultant pressure: 25760 lbs. per square foot

$$\text{Area of section 5: } \frac{1}{2} [12+12] = 12 \text{ sq. ft.}$$

$$\text{Weight of sections 1, 2, 3, 4 and 5: } [12+12+12+12+12] \times 150 = 9000 \text{ lbs.}$$

$$\text{Water pressure 100 foot depth: } \frac{62.5 \times 100}{2} = 3125 \text{ lbs.}$$

Resultant pressure: 42000 lbs. per square foot

$$\text{Area of section 6: } \frac{1}{2} [12+12] = 12 \text{ sq. ft.}$$

$$\text{Weight of sections 1, 2, 3, 4, 5 and 6: } [12+12+12+12+12+12] \times 150 = 10800 \text{ lbs.}$$

$$\text{Water pressure 120 foot depth: } \frac{62.5 \times 120}{2} = 3750 \text{ lbs.}$$

Total resultant pressure: 55760 lbs. per square foot

RETAINING SECTION (concluded):-

Factor of safety against over-turning:

$$\frac{\text{Resisting Moment}}{\text{Overturning Moment}} = \frac{835763 \times 55.8}{488280 \times 41.7} = 2.2$$

Factor of safety against sliding:

Assuming coefficient of friction of concrete on

rock as .85

$$\frac{835763 \times .85}{488280} = 1.4$$

$$p_1 = \frac{R}{l} = \frac{966700}{75.8} = 12753 \text{ lbs.}$$

$$p_2 = \frac{6Rb}{l^2} = \frac{6 \times 966700 \times 10.8}{(75.8)^2} = 10902 \text{ lb.}$$

$$p_1 - p_2 = 12753 - 10902 = 1851 \text{ # min.}$$

$$p_1 + p_2 = 12753 + 10902 = 23655 \text{ # max.}$$

SPILLWAY SECTION:-

Area of section 1: $9 \times 1.43 = 12.87 \text{ sq. ft.}$ Area of section 2: $\frac{2}{3} [9 \times 10.08] = 60.48 \text{ sq. ft.}$ Area of section 3: $\frac{15}{2} [20.5 + 11.5] = 240 \text{ sq. ft.}$

Total weight of sections 1, 2 and 3:

$$[12.87 + 60.48 + 240] 150 = 47000 \text{ lbs. / cu. ft.}$$

Total water pressure: $\frac{62.5 \times 24^2}{2} = 25600 \text{ lbs. / sq. ft.}$

Let h = height of section

d = depth of water on crest

Then point of application of water pressure is $\frac{h+3d}{h+2d} \times \frac{h}{3}$
from the bottom of section. $\frac{24+15}{24+10} \times 8 = 9.17'$

Total resultant pressure: 52200 lbs. per sq. ft.

Factor of safety against over-turning:

$$\frac{\text{Resisting Moment}}{\text{Overturning Moment}} = \frac{47000 \times 13.2}{25600 \times 9.17} = 2.6$$

Factor of safety against over-turning:

$$F.S. = \frac{\text{Overturning Moment}}{\text{Resisting Moment}} = 2.5$$

Factor of safety against sliding:

Assuming coefficient of friction of concrete on

rock as .35

$$F.S. = \frac{W \times \mu}{H} = \frac{12,000 \times .35}{4,000} = 1.05$$

$$F.S. = \frac{W}{H} = \frac{12,000}{4,000} = 3.0$$

STABILITY FACTORS:

- Area of section 1: $2 \times 1.43 = 2.86 \text{ sq. ft.}$
- Area of section 2: $\frac{1}{2} [2 \times 10.0 + 20 \times 1.43] = 15.0 \text{ sq. ft.}$
- Area of section 3: $\frac{1}{2} [2 \times 5.1 + 11 \times 2.0] = 8.0 \text{ sq. ft.}$

Total weight of sections 1, 2 and 3:

$$[2.86 + 15.0 + 8.0] \times 150 = 4,700 \text{ lbs.}$$

Total water pressure: $\frac{2.86 \times 2.0}{2} + \frac{15.0 \times 2.0}{2} + \frac{8.0 \times 2.0}{2} = 2,000 \text{ lbs.}$

Net height of section

depth of water on crest

Then point of application of water pressure is $\frac{2.0 \times 2.86}{2} + \frac{2.0 \times 15.0}{2} + \frac{2.0 \times 8.0}{2} = 12.1 \text{ ft.}$ from the bottom of section.

Factor of safety against over-turning:

$$F.S. = \frac{W \times \mu}{H} = \frac{12,000 \times .35}{4,000} = 1.05$$

SPILLWAY SECTION (concluded):-

Factor of safety against sliding:

Assuming coefficient of friction of concrete on
rock as .85

$$\frac{47000 \times .85}{25600} = 1.5$$

$$p_1 = \frac{R}{L} = \frac{52200}{18} = 2900 \text{ lbs.}$$

$$p_2 = \frac{6Rb}{L^2} = \frac{6 \times 52200 \times 1.85}{(18)^2} = 1788 \text{ lbs.}$$

$$p_1 - p_2 = 2900 - 1788 = 1112 \text{ lbs. (minimum)}$$

$$p_1 + p_2 = 2900 + 1788 = 4688 \text{ lbs. (maximum)}$$

THE UNIVERSITY OF CHICAGO

DEPARTMENT OF CHEMISTRY

RECEIVED AT THE UNIVERSITY OF CHICAGO

NOV. 10, 1930

FROM

DR. J. H. HARRIS

TO

DR. J. H. HARRIS, CHICAGO, ILL.
 100 EAST 58TH STREET, NEW YORK 22, N. Y.

PIPE-LINE

The water is delivered to the power house through a riveted steel pipe, twelve feet in diameter and eleven hundred feet long, and through two six foot pipes which act as penstocks for the turbines in the power house. The connection between the single large pipe and the two smaller ones is made by means of a surge tank forty feet in diameter and fifty-eight feet high, which is placed on a high spot about four hundred feet from the power house.

The intake of this twelve foot pipe is at elevation 640, the crest of the dam at 675, giving a head of thirty-five feet, and was designed to carry twelve hundred cubic feet of water per second.

Using the formula $h = f \frac{l}{d} \times \frac{v^2}{2g}$, where

h = loss of head

f = coefficient

l = length

d = diameter

v = velocity

g = gravity

and assuming a 12 foot pipe

$$h = .01 \frac{1050}{12} \times \frac{112.36}{64.3}$$

therefore $h = 1.53$

$$\text{Slope, } S = \frac{h}{l} = \frac{1.53}{1050} = .00145$$

Then from

$$V = c \sqrt{rs}$$

$$\text{since } Q = AV \\ V = \frac{Q}{A} = \frac{1200}{113} = 10.6$$

The water is delivered to the power house through a riveted steel pipe, twelve feet in diameter and eleven hundred feet long, and through two six foot pipes which act as penstocks for the turbines in the power house. The connection between the single large pipe and the two smaller ones is made by means of a large tank forty feet in diameter and fifty-eight feet high, which is fixed on a high spot about four hundred feet from the power house. The intake of this twelve foot pipe is at elevation 840, the crest of the dam at 875, giving a head of thirty-five feet, and was designed to carry twelve hundred cubic feet of water

per second.

Using the formula $H = f \frac{L}{d^5} \times \frac{Q^2}{2g}$, where

H - head of water

f - coefficient

L - length

d - diameter

Q - velocity

g - gravity

and assuming a 12 foot pipe

$$H = 0.1 \frac{1000}{12^5} \times \frac{12^2}{2 \times 32.2}$$

therefore $Q = 1.35$

$$Q = \frac{1.35 \times 12^2}{4} = 12.15 \text{ cfs}$$

$$V = 0.12$$

$$Q = \frac{12.15}{1.35} = 9.0$$

where c = constant

r = hydraulic mean radius: for full pipe $r = \frac{d}{4}$, since pipe must be designed for maximum.

$$S = \frac{h}{l}$$

Substituting values

$$v = 190 \sqrt{3 \times .00145}$$

$$12.35 = \text{feet per second.}$$

This velocity is not too large because maximum amount of water will not be used and consequently the velocity will not reach this figure.

There fore use 12 foot pipe

Thickness of pipe:

Allowable tensile strength of pipe = 16000 lbs. per square inch

Head = 35 feet

Head (in feet) $\times .434$ = lbs. per square inch

Then $W \times \frac{d}{2} = t \times 16000$;

$$35 \times .434 \times 6 \times 12 = t \times 16000 \times 12$$

$$\therefore t = .054 = \frac{1}{16}''$$

Allowing for water hammer, which occurs and also for stiffness of pipe use $\frac{3}{8}$ inches.

Therefore Pipe Dimensions are as follows:-

Diameter:- 12 feet

Thickness:- $\frac{3}{8}$ inches

Length of Plate:- 6 feet

where c = constant

r = hydraulic mean radius for full pipe $r = \frac{D}{4}$, since
pipe must be designed for maximum.

$$V = 120 \sqrt{S} \times 0.0148$$

12.38 feet per second.

This velocity is not too large because maximum amount of
water will not be used and consequently the velocity will not
reach this figure.

There fore use 12 foot pipe

Thickness of pipe

Allowable tensile strength of pipe = 18000 lbs. per square inch

Head = 35 feet

Head (in feet) $\times .434$ = lbs. per square inch

Then $W \times 4.4 \times 18000$

$$35 \times .434 \times 4.4 \times 18000 \times 12$$

$$12.38 \times \frac{1}{12} = .027 \text{ in.}$$

Allowing for water hammer, which occurs and also for stiffness
of pipe use 1/2 inch.

Therefore Pipe Dimensions are as follows:-

Diameter:- 12 feet

Thickness:- 1/2 inch

Length of Pipe:- 3 feet

RIVETS:-

Rivets should be $\frac{1}{4}$ x thickness of thickest plate + $\frac{3}{16}$: then

$$\frac{5}{4} + \frac{3}{8} = \frac{15}{32} + \frac{6}{32} = \frac{21}{32}; \quad \text{Therefore use } \frac{3}{4} \text{ " rivets.}$$

The spacing should be not less than $\frac{1}{2}$ x diameter + $\frac{1}{2}$

$$\frac{3}{2} \times \frac{3}{4} = \frac{9}{8} \times \frac{4}{8} = \frac{13}{8} = 1 \frac{5}{8} \text{ " use } 2 \text{ " .}$$

The girth seams are lap jointed, single riveted and the longitudinal seams lap jointed, double riveted. Considering six foot section, the pressure is found to be

$$1094 \times 6 \times 12 = 78720 \text{ lbs.}$$

Allowing 12000 lbs. for double shear, then $\frac{78720}{12000} = 7+$;

therefore 8 rivets per foot will be used.

The diameters of adjacent 6 foot lengths vary by twice the thickness of the plate, forming inside and outside sections alternately, and angle irons 5" x 3" are placed at every other joint, thus strengthening the pipe between supports. The supports being concrete piers every 12 feet except through one section where they are placed every 10 feet. At this section the pipe is suspended 15 feet and the concrete piers are 20 feet high, reaching to the center line of the pipe. They are 2 feet thick and 16 feet wide.

Rivets should be $N \times$ thickness of thickest plate. 30 : then

$$\text{Therefore use } \frac{3}{4} \text{ rivets.}$$

The spacing should be not less than $\frac{1}{2} \times$ diameter.

$$\frac{1}{2} \times \frac{3}{4} = \frac{3}{8} \text{ or } 0.375 \text{ feet}$$

The rivets are lap joined, single riveted and the

the rivets are lap joined, single riveted and the

six foot section, the pressure is found to be

$$1004 \times 6 \times 12 = 72288 \text{ lbs}$$

Allowed 12000 lbs. for double shear, then

therefore 6 rivets per foot will be used.

The diameter of adjacent 6 foot joints vary by twice

the thickness of the plate, forming inside and outside sections

alternately, and rivets from 6" x 6" are placed at every other

joint, thus strengthening the pipe between supports. The

supports being concrete piers every 12 feet except through one

section where they are placed every 10 feet. At this section

the pipe is suspended 12 feet and the concrete piers are 12

feet high, reaching to the center line of the pipe. They are

2 feet thick and 12 feet wide.

The alignment of the pipe in a vertical plane consists of one long tangent about 1100 feet in length, running from the dam to the surge tank at the constant elevation of 640, and under a head of 35 feet. The drop in about 400 feet from the tank to the power house, is 90 feet from center line of pipe to center line of turbines, making a total head of 125 feet at the turbine.

Horizontally, there is a tangent 300 feet long running from the dam, then at an angle of about 62° another tangent 800 feet long to center line of tank. An expansion joint is provided fifteen feet from the end of first section; the end of the curve on first section being covered sufficiently deep to do away with expansion and contraction. The upper end of the first section has a fixed connection with the dam, and the lower end of the second section is rigidly connected to the tank.

At the expansion joint the shell of the adjacent pipe sections are increased from $\frac{3}{8}$ inches to $\frac{1}{2}$ inches; one pipe enters the other for not more than 30 inches, the rivets in the engaged section being counter-sunk. Between the inner pipe, and a sleeve $12 \times \frac{1}{2}$ inches, which project beyond the outer pipe, a packing such as hemp will be used, and secured by small plates riveted or bolted to the flange of the sleeve. Similar joints are provided for by elbows in the smaller pipes leading from the tank to the power house.

The alignment of the pipe in a vertical plane consists of one long tangent about 1100 feet in length, running from the dam to the surge tank at the constant elevation of 440, and under a head of 35 feet. The drop in about 400 feet from the tank to the power house, is 30 feet from center line of pipe to center line of turbines, making a total head of 140 feet at the turbine.

Horizontally, there is a tangent 300 feet long running from the dam, then at an angle of about 50° another tangent 300 feet long to center line of tank. An expansion joint is provided fifteen feet from the end of first section; the end of the curve on first section being covered sufficiently deep to go away with expansion and contraction. The upper end of the first section has a fixed connection with the dam, and the lower end of the second section is rigidly connected to the tank.

At the expansion joint the shell of the adjacent pipe sections are bolted from outside and the rivets are riveted on the other for not more than 30 inches, the rivets in the engaged section being counter-sunk. Between the inner pipe, and a sleeve is $1\frac{1}{2}$ inches, which project beyond the outer pipe, a packing such as hemp will be used, and secured by small plates riveted or bolted to the flange of the sleeve. Similar joints are provided for by sleeves in the smaller pipes leading from the tank to the power house.

- SURGE TANK:

The surge tank is used to take up water hammer occurring when the turbines are shut off, and saving the pipe, which might be bursted. The surge tank will be built 15 feet above crest of the dam, making the elevation of top of tank 690.

The tank was designed in three sections as follows:

Let w = weight of cubic foot of water = 62.5

h = height of section to be designed

d = diameter

A_s = area of steel

f_s = unit stress allowable = 16000

Therefore, for the first section (twenty-three feet)

$$62.5 \times 58 \times 20 = A_s \times 16000$$

$$A_s = 4.5 \text{ square inches}$$

$$A_s = 358 = \frac{5}{16} \text{ inches}$$

Allowing for water hammer, make plate $\frac{1}{2}$ inch thick.

Second section (twenty feet)

$$62.5 \times 35 \times 20 = A_s \times 16000$$

$$A_s = 2.73 \text{ sq. ins.} \quad \therefore t = \frac{2.73}{12} = .23 = \frac{1}{4}''$$

Allow $\frac{3}{16}$ inches for water hammer, plate will be $\frac{7}{16}$ inches thick.

Third section (fifteen feet)

$$62.5 \times 15 \times 20 = A_s \times 16000$$

$$A_s = 1.17 \text{ sq. in.} \quad \therefore t = \frac{1.17}{12} = .093''$$

For stiffness and safety, the thickness of this section will be made $\frac{3}{8}$ of an inch.

Notes:

The surge tank is used to take up water hammer occurring when the turbines are shut off, and leaving the pipe, which might be torn out. The surge tank will be built 15 feet above crest of the dam, making the elevation of top of tank 260.

The tank was designed in three sections as follows:

1st a weight of cubic foot of water = 62.5

2nd height of section to be designed

3rd diameter

4th area of steel

5th unit stress allowable

Therefore, for the first section (Twenty feet)

$62.5 \times 20 = A \times 10000$

$A = 4.8$ square inches

$A = 3.883 = \frac{\pi}{4} d^2$ inches

Allowing for water hammer, make plate 1/2 inch thick.

Second section (Twenty feet)

$62.5 \times 20 = A \times 10000$

$A = 4.8$ square inches

Allow 1/2 inches for water hammer, plate will be 1/2 inches thick.

Third section (Fifteen feet)

$62.5 \times 15 = A \times 10000$

$A = 3.6$ square inches

For stiffness and safety, the thickness of this section

will be made 1/2 of an inch.

Rivets for tank:

$$\frac{5}{4} \times \frac{1}{2} = \frac{5}{8} ; \quad \frac{5}{8} + \frac{3}{16} = \frac{13}{16} \quad \therefore \text{use } \frac{7}{8}'' \text{ rivets.}$$

The spacing should be not less than

$$\frac{3}{2} \times \frac{7}{8} = \frac{21}{16} + \frac{8}{16} = \frac{29}{16} = 2 \text{ inches. (approx.)}$$

The stress at the bottom must be equal for every seam, then $62.5 \times 55 \times 20 = 68750$ lbs. The allowable stress on each rivet is 7500 lbs. per square inch. Then $\frac{68750}{7500} = 9.1$; therefore 10 rivets are required. The girth seams are riveted two inches to make a water-tight connection.

POWER-HOUSE.

The power-house will be placed on the present site of an old grist mill, located on the north bank of the stream at a distance of about fifteen hundred and fifty feet from the site of the dam. The power-house will be built of concrete both substructure and superstructure. Its outside dimensions are 103 feet 4 inches x 49 feet 4 inches. The roof trusses are of steel and supported on concrete pilasters. The covering consists of corrugated red tile roofing. A traveling crane of twenty tons capacity, operated by hand power, traverses the building, the track girders being carried by the concrete pilasters. This building contains all the hydraulic units and electrical appurtenances, offices, and machine shop. The turbine units, transformers and machine shop are placed on the first floor. The switch-board gallery is placed along the south end of the building, and the top floor is reserved for bus bars and switch cells.

The available horse-power (7200) will be developed by three horizontal shaft S. Morgan Smith turbines each fifty-four inches in diameter, with a capacity of 2400 h.p. at 360 r.p.m. Each unit carries its own exciter unit mounted on same shaft. The turbines are each direct connected to three phase alternating current generators, having an out-put of 1800 k.w. at 360 r.p.m.

The transformers are situated on the main floor along the east side of the power-house. They receive the current

The power-house will be placed on the present site of an old grist mill, located on the north bank of the stream at a distance of about fifteen hundred and fifty feet from the site of the dam. The power-house will be built of concrete both in its structure and superstructure. Its outside dimensions are 103 feet 4 inches x 40 feet 4 inches. The roof trusses are of steel and supported on concrete pillars. The covering consists of corrugated red tile roofing. A traveling crane of twenty tons capacity, operated by hand power, traverses the building, the track system being carried by the concrete pillars. This building contains all the hydraulic units and electrical apparatus, electric, and machine shop. The turbine units, transformers and machine shop are placed on the first floor. The exhaust-steam gallery is placed along the south end of the building, and the top floor is reserved for bus bars and switch cells.

The available horse-power (V.M.O.) will be developed by three horizontal shafts of Morgan Smith turbines, each fifty-four inches in diameter, with a capacity of 3,000 h.p. at 300 r.p.m. Each unit carries its own exciter unit mounted on same shaft. The turbines are each fitted connected to three phase alternating current generators, having an output of 1,000 h.p. at 300 r.p.m.

The transformers are situated on the main floor along the east end of the power-house. They receive the current

from the generators, and step up the voltage to 33000 at which pressure the current will pass into the transmission lines.

For the present, two units of twenty-four hundred h.p. each are to be installed and provision in size of pen-stocks, power-house etc. left for a third unit of twenty-four hundred h.p. to be installed latter when increased market demand shall justify same.

IN DETERMINING THE STRESS DISTRIBUTION THE FOLLOWING FORMULAE ARE USED:

1. THE STRESS DISTRIBUTION IS ASSUMED TO BE LINEAR:

Dead load = 10 pounds per square foot.

" " " " " "

Live load = 100 pounds per square foot.

The formula used for bending moment was:

$$M = \frac{1}{10} W L^2$$

where W = total load on beam

$$L = \text{length of beam}$$

NOTE:

Dead load = 10 pounds per square foot.

" " " " " "

$$\text{Bending moment, } M = \frac{1}{10} W L^2$$

COLUMNS: - supporting third floor, the following loading was

assumed:

Dead load = 10 pounds per square foot.

" " " " " "

Yale Wall of Reinforced Concrete was used

in determining the size of column and amount of reinforcement.

In all the above calculations the allowable stresses

in the concrete were taken as:

Compression ----- 300 pounds per square inch.

" " " " " "

" " " " " "

Weight of concrete ----- 150 " " " "



Drainage Area of East Canada Creek Shaded

PROPOSED EAST CREEK DEVELOPMENT
 INGHAM MILLS
 IMMEDIATE AND VICINITY
 J. W. Buck, H. J. Newmyer, G. D. Lettermann
 THE SIS ①





PROPOSED EAST CREEK DEVELOPMENT
AT
INGHAM MILLS, NEW YORK
J. W. Beck, R. L. Conway, G. D. Lettermann
THE 515 (2)

1899

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS N.Y.




1900

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS, N.Y.



1901

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS, N.Y.




1902

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS, N. Y.




1903

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS, N. Y.




1904

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS N.Y.




1905

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS, N.Y.



1906

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS, N.Y.



1907

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS, N.Y.



1908

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS N.Y.

SECOND - FEET

3400
3200
3000
2800
2600
2400
2200
2000
1800
1600
1400
1200
1000
800
600
400
200
0

Jan Feb Mch Apr May June July Aug Sept Oct Nov Dec

MONTH






1909

Mean Monthly Discharge Curve
East Canada Creek
INGHAM MILLS, N.Y.

SECOND - FEET


3400
3200
3000
2800
2600
2400
2200
2000
1800
1600
1400
1200
1000
800
600
400
200
0




Jan Feb Mch Apr May June July Aug Sept Oct Nov Dec

MONTH


DISCHARGE IN SECOND- FEET





1907
Daily Discharge Curve
East Canada Creek
INGHAM MILLS N.Y.





1907
Discharge Curve
Canada Creek
MILLS N.Y.












DOWNSTREAM ELEVATION OF DAM AND SPILLWAY
Scale - 1 inch = 20 ft




DAM ELEVATION OF DAM AND SPILLWAY


Scale - 1 inch = 20 ft

PROPOSED EAST CREEK DEVELOPMENT
AT
INGHAM MILLS, NEW YORK
H. W. Buck, H. J. Tenney, & J. D. Lettermann
THESIS 5






CROSS SECTION OF DAM
Scale - 1 inch = 20 ft.



CROSS-SECTION THRU INTAKE





CROSS SECTION THRU SPILLWAY
Scale - 1 inch = 4 ft.



FLASH BOARDS ARRANGEMENT
Scale - 1 inch = 1 foot







Scale - $\frac{1}{2}$ inch = 1 Ft.

PROPOSED EAST CREEK DEVELOPMENT
SLUICE AND GATE
OPERATING STAND
L. W. Buck, H. H. Harny, G. D. Lettermann
THE S/S ⑦







SECTION THROUGH 1/2 OF 12" NOZZLE



IRON LADDER RIVETED TO SIDE OF TANK
ONE IN SIDE & ONE OUT SIDE FOR ENTRY
HEIGHT OF TANK 15' 0"




SECTION THROUGH 1/2 OF 12" PENSTOCK CONNECTION




EAST CANADIAN CREEK DEVELOPMENT
DETAIL OF 40" DIA SURGE TANK FOR
12" DIA PENSTOCK


G.W. BUCK WILKINSON G. LITTELMANN
THESE









EAST CANADA CREEK DEVELOPMENT
PIPE LAYOUT
PLAN AND PROFILE
INGHAM MILLS NY
G.W. DUCK, WOODBURY CO. LETTERMAN
THESES






4 B
THE LOCATION OF WINDOWS ON THE TWO SIDES
& FRONTS ARE THE SAME

MAIN FLOOR PLAN




SECOND FLOOR PLAN



BASEMENT FLOOR PLAN

PROPOSED EAST CREEK DEVELOPMENT
AT
INGHAM MILLS, NEW YORK
BY
R. M. Buck & J. J. Murray, Architects
THE O. S. I. S.




Architectural elevation drawing of the front facade of the 'Maison de la Vierge' in Le Mans, France. The drawing shows five windows with varying shapes (rectangular, arched) and five circular medallions below them. Each medallion contains a small figure. The drawing is on a blue background with white lines.


PROPOSED EAST CREEK DEVELOPMENT
AT
VINGHAM MILLS, NEW YORK
843-2-44 Henry, 52 State and
THE 315 (14)








PROPOSED EAST CREEK DEVELOPMENT
AT
INGHAM MILLS, NEW YORK
E. H. Duck, J. H. Beatty, G. A. Fettermann
THESES








FRONT ELEVATION OF POWER HOUSE

PROPOSED EAST CREEK DEVELOPMENT
AT
INGHAM MILLS, NEW YORK
E. M. Buck, A. J. Rosney, G. L. Dettmerman
THE SIS





SIDE ELEVATION OF POWER HOUSE

PROPOSED EAST CREEK DEVELOPMENT
 AT
 INGHAM MILLS NEW YORK
 S. M. Bach, H. J. Henry, & L. L. Lottensman
 THE S. S. 16

